Galvanized Line Service Replacement Summary:

The city will:

- Replace the private galvanized water line from the meter to the point of building entry that is most practical (building inlet) with PEX water line.
- Dig a simple trench to replace the line from the meter to the house.
- Give you at least 48 hours notice prior to beginning replacement.
- Install related fittings and reconnection to interior plumbing outside the building foundation.
- Avoid excess damage to landscaping as much as possible
- Basic restoration of landscaping: basic backfill, seeding, and surface grading.
    - **Does not include:** sod replacement, decorative landscape, private irrigation lines, watering, etc.
- The City or the City's contractor will provide a minimum 12-month workmanship warranty for the installed service line.
- Provide a pitcher filter with 6 months of filters for use if you so desire.
- Conduct follow up testing at 3-6 months installation as required by regulation.

The city will not:

- Replace trees, bushes, or other landscaping that is removed or damaged during the line replacement process.
- Replace any interior plumbing or connections unless needed by unexpected circumstances.
- Perform any additional service beyond what is required from the water meter to the building inlet.

What is expected of you:

- Complete the service line survey at https://lawrenceks.gov/mso/lead-survey if you have not already.
- Sign a waiver for service line replacement and send it to leadandcopper@lawrenceks.gov
- Allow access to the yard, interior service line location, and coordinate with city field crews during installation time frame. Participate in a single tap sampling 3-6 months after replacement, as required by regulation.